

**SCHEDULE - A**

**WORK:** Proposed construction of compound wall around OSR land in T.S.No.54/1 pt., 54/2 pt., 54/3 pt., 56 pt., Block No.6 of Venkatapuram village at Sardar Patel Road in Dn.139.

**Z.O.IX.C.No.B1/ 1790-32/ 10**

**Rates: 2009-10; Zone: South**

<b>Sl. No.</b>	<b>Qty.</b>	<b>Description of Work</b>	<b>Sch. No.</b>	<b>Rate</b>	<b>Per</b>	<b>Amount (Rs.)</b>
1	55 cum	Dismantling brick or stone masonry in cement mortar walls under 3m high	315	72.60	1cu.m.	3993
2	76 No.	Providing double under reamed pile 30cm dia 3.66m deep and 3.58m from G.L. in RCC 1:1.5:3 (excluding the cost of reinforcement)	766	1753.90	1No.	133296
3	21 cum	Earth work excavation for foundation excluding refilling	357	63.30	1cu.m.	1329
4	11 cum	Supplying and filling with karanodai sand for foundation and basement	362	361.90	1cu.m.	3981
5	11 cum	Cement concrete work in C.M1:4:8 using stone jelly 40mm gauge including curing. Ramming, etc, complete.	418	1854.80	1cu.m.	20403
6	115 sqm	Supplying and erecting shuttering for plane surface in foundation and basement for RCC column footings, plinth beam, staircase steps, critical piers, etc.	432A	238.90	1sq.m.	27474
7	170 sqm	Supplying and erecting centering for RCC square and rectangular columns top and bottom slabs of boxing sill slabs, etc.	432B	330.00	1sq.m.	56100
8	6400 kg	Supplying R.T.Steel upto 16mm dia including fabricating, tying with binding wire, laying in position, etc, complete for RCC works	431A	38.40	1kg	245760
9	30 cum	R.C.C.work in C.M.1:1:5:3 using 12 to 20mm gauge broken stones including curing, etc.,	427	3411.80	1cu.m.	102354
10	40 cum	Brick work in C.M.1:6 for 23cm thick walls upto basement.	452	2169.00	1cu.m.	86760
11	400 sqm	Plastering with C.M.1:4, 12mm thick.	518	67.60	1sq.m.	27040
12	350 sqm	Plastering with C.M.1:3, 12mm thick.	516	75.00	1sq.m.	26250
13	160 sqm	Supplying and fixing M.S.Grill of approved Designs for Windows, Ventilators and gates etc. with priming coat of Paint.	662C	1032.90	1sq.m..	165264
14	400 kg	Supplying and fixing M.S.Grill gate including one coat of approved primer etc. complete.	662B	50.80	1Kg.	20320

Signature of Tenderer

Sl. No.	Qty.	Description of Work	Sch. No.	Rate	Per	Amount (Rs.)
15	5 sqm	Making and fixing M.S.Sheet gate without primer etc. complete. (Relevant I.S.I. STD)	662A	1980.00	1sq.m..	9900
16	20 m	Supplying and jointing 50mm dia G.I.Pipe (M.W.1)	684	382.00	1m	7640
17	2 No.	Supplying and providing 50mm size brass lock. (Relevant I.S.I. Std.)	664	120.00	1No.	240
18	750 sqm	White washing two coats over new plastered surface.	525	7.10		
		Painting the new plastered walls with two coats of cement based paint including preparing the surface, curing, etc. (Relevant I.S.I. STD)	541	32.50		
				<u>39.60</u>	1sq.m.	29700
19	270 sqm	Painting new iron work two coats with ready mixed paint of superior quality and approved colour (I.S.I. STD).	556	37.40	1sq.m.	10098
20	140 sqm	Art work as per the direction of department official, over Oil Painting with first class quality and approved colour including a priming coat with thorough scrapping clean removal of dirt, etc. and including necessary plaster of paris, wherever required, etc. complete (Relevant ISI STD), including putty works	Art2	356.49	1sqm	49909
<b>TOTAL</b>						<b>1027811</b>

Signature of Tenderer