

பம்மல் நகராட்சி

காஞ்சிபுரம் மாவட்டம்

ந.க.எண். 718 /2009 / இ1

நாள்: 16-09-2010

ஒப்பந்தப்புள்ளி அறிக்கை

1998ஆம் ஆண்டு தமிழ்நாடு ஒளிவுமறைவற்ற ஒப்பந்தப்புள்ளிகள் சட்டம் (தமிழ்நாடு சட்டம் 43/1998) கீழ் அறிவிக்கப்படுகிறது.

பம்மல் நகராட்சியின் சார்பாக செயல் அலுவலர் அவர்களால் சுவர்னஜெயந்தி ரோஜ்கார் யோஜனா திட்டம் 2010-11ன் கீழ் பணியினை செய்து முடிக்க தேவையான பொருட்கள் சப்ளை செய்ய மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகள் பதிவு பெற்ற ஒப்பந்ததாரர்களிடமிருந்து 07.10.10ம் தேதி வியாழக் கிழமை பிற்பகல் 3.00 மணிவரை (அலுவலக கடிசை நேரத்தின்படி) செயல் அலுவலர் அல்லது அவரது அங்கீகாரம் பெற்றவர்களால் பூர்த்தி செய்யப்பட்ட ஒப்பந்தப்புள்ளிகள் பெற்றுக் கொள்ளப்படும். பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் அனைத்தும் அன்று பிற்பகல் 3.30 மணி அளவில் வருகை தந்திருக்கும் ஒப்பந்ததாரர்கள் முன்னிலையில் ஒப்பந்தப்புள்ளி உறைகள் திறக்கப்படும்.

பணி தொடர்பான ஒப்பந்தப்புள்ளி படிவங்கள் இந்நகராட்சி அலுவலகத்தில் வேலை நாட்களில் 06.10.10 அன்று மதியம் 3.00 மணி வரை உரிய தொகை செலுத்தி பெற்றுக் கொள்ளலாம். பணி தொடர்பான இதர விவரங்களை நகராட்சி பொறியியல் பிரிவிலோ அல்லது <http://municipality.tn.gov.in/tenders>, <http://www.tenders.tn.gov.in> என்ற இணையத்தளத்தின் மூலமும் தெரிந்து கொள்ளலாம்.

ஒப்பந்தப்புள்ளி கோரும் பணியின் விவரம்

வ. எண்	வார்டு எண்	பணிகளின் விவரம்	மதிப்பீடு தொகை ரூ.	ஒப்பந்தப்புள்ளி படிவ விலை ரூ.	காப்புறுதி தொகை 1% ரூ	சப்ளை செய்ய வேண்டிய கால அளவு
1	2	3	4	5	6	7
1	1	வார்டு எண். 12, மூங்கில் ஏரி கஸ்தூரிபாய் குறுக்குத் தெருவில் சிமெண்ட் சாலையோடு கூடிய மழைநீர் வடிகால்வாய் அமைக்கும் பணிக்கு தேவையான சாலை பொருட்கள் சப்ளை செய்தல்	3,25,000/-	845/-	3250/-	30 நாட்கள்

பெறுநர்:

1. பதிவு செய்யப்பட்ட அனைத்து ஒப்பந்ததாரர்கள், பம்மல் மூன்றாம் நிலை நகராட்சி.
2. நகர மன்ற தலைவர், துணைத் தலைவர் மற்றும் அனைத்து உறுப்பினர்கள், பம்மல் மூன்றாம் நிலை நகராட்சி.
3. அலுவலக விளம்பரப் பலகையில் ஒட்டி விளம்பரம் செய்ய
4. செயல் அலுவலர், அனகாபுத்தூர், புழுதிவாக்கம், மறைமலைநகர், வளசரவாக்கம் நகராட்சிகளின் - அலுவலக விளம்பர பலகைக்கு.

நகல்:

1. நகராட்சிகள் நிர்வாக இயக்குநர், எழிலகம், சேப்பாக்கம், சென்னை - 5 அவர்களின் தகவலுக்கு பணிந்து சமர்ப்பிக்கப்படுகிறது.
2. மண்டல நகராட்சிகள் நிர்வாக இயக்குநர், செங்கல்பட்டு மண்டலம். அவர்களின் தகவலுக்கு பணிந்து சமர்ப்பிக்கப்படுகிறது.
3. செயல் அலுவலர், அனகாபுத்தூர், புழுதிவாக்கம், மறைமலைநகர், வளசரவாக்கம் நகராட்சிகளின் அலுவக விளம்பர பலகைக்கு.

செயல் அலுவலர்
பம்மல் நகராட்சி

Date of Tender :

Issued to :

Schedule Cost Rs :

Challan No.& Date :

Municipal Engineer
Pammal Municipality

PAMMAL MUNICIPALITY **TENDER SCHEDULE**

- a) The quantities given here are those upon which lump sum tender cost of the work based but they are subject to alternations, omissions / deductions or additions as provided for the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates noted below this governing payment for the contract, as set forth in the preliminary a specification and other conditions as specification of the Chennai details standard specification and other conditions as specification of the contract.
- b) It is to be expressly understood that the measured work is to taken net (not with standing and customer practice to the contrary) according to the actual quantities when in places and finished according to the drawing or as many be ordered from time to time the cost calculated by measurement or weight, at the respective prices, without any additional charge for any necessary or contingent therewith. The rates quoted are for works in site and complete in every report.

Name of Work : Providing Strom Water Drain to Moongil Eri Kasthuribai Cross Street in Ward No. 12

Estimate Cost : **325000**

Signature of Contractor

Name of Scheme : **SJSRY 2010-11**

Earnest Money Deposit Rs : **3250**

Tender Date / Time :

PAMMAL MUNICIPALITY

Tender Schedule for the Work of Providing Strom Water Drain to Moongil Eri Kasthuribai Cross Street in Ward No. 12

Est Amt: 325000/-

SI No	Qty	Description of Work	Unit Per	Rate in Figures	Rate in Words	Amount	Remarks
1	1.00	Earthwork excavation in all soils except hard rock soil including de-watering wherever necessary and refilling the earth after completion of work etc., complete as per the standard specification.	One Cubic Metre				
2	1.00	Filling with dry river Sand including cost and conveyance of material, and labour for placing, watering and consolidation etc., complete as per specification	One Cubic Metre				
3	1.00	Plain cement concrete 1:5:10 (one cement five sand and ten aggregate) mix using 40 mm ISS HBG metal including cost of material, conveyance and labour for mixing, placing and consolidation and watering for curing etc., complete as per specification	One Cubic Metre				
4	1.00	Providing Steel centering and shuttering using 10cm to 15cm dia casurina post and M.S sheet of size 60cm X 90 cm etc., complete as per standard specification for Drain	One Square Metre				
5	1.00	Plain cement concrete 1:3:6 (one cement three sand and six aggregate) mix using 20mm ISS HBG metal including cost and conveyance of material, and labour for mixing, placing, consolidation and watering for curing etc., complete as per specification	One Cubic Metre				
6	1.00	Flooring plastering with cm 1:5 (one cement and five sand) including cost and conveyance of material and labour charges for placing curing etc., complete as per specification	One Square Metre				
7	1.00	Removal of excess earth with minimum lead of 2Km including labour, Transport and loading and unloading etc complete as per standard specification	One Cubic Metre				
8	1.00	Providing & Laying Granular Sub base as per Table No. 400-1/400-2 and Grading III or MORTH Revision IV with and any other Granular material or a combanitation those of for 150mm thick to give a CBR of 20 on prepared sub grade in accordance with the requirements of the specifications for sand, Gravel & 6mm Aggregate Mix Hire Charges and Labour Charges for San Gravel Compaction	One Cubic Metre				
9	1.00	Plain Cement Concrete 1:4:8 mix Using 40mm ISS HBG metal including all cost conveyance of materials and labour charges etc. complete as per standard specification	One Cubic Metre				
10	1.00	Centering and shuttering for all item of PCC/RCC works including labour charges etc., complete	One Square Metre				
11	1.00	Plain cement concrete 1:2:4 (one cement two sand and four aggregate) mix using 20 mm ISS HBG metal including cost and conveyance of material, and labour for mixing, placing, consolidation and watering for curing etc., complete as per specification	One Cubic Metre				
12	1.00	Supply and fixing of Bitumen Pad for Expantion joint etc complete as per direction of departmental officers	One Square Metre				

(Approved (12) Fourteen Items Only)

No. of Corrections :

No. of Overwrittings :

Signature of the Contractor

**Overseer
Pammal Municipality**

**Municipal Engineer
Pammal Municipality**