

**SCHEDULE - A**

**WORK:** Laying Cement Concrete Road inside the Burial Ground at Velachery Main Road in Dn.141 under BSUP scheme.

**Z.O.IX.C.No.B1/ 1790-36/ 10**

**Rates: 2009-10; Zone: South**

<b>Sl. No.</b>	<b>Qty.</b>	<b>Description of Work</b>	<b>Sch. No.</b>	<b>Rate</b>	<b>Per</b>	<b>Amount (Rs.)</b>
1	233 cum	Laying C.C. 1:4:8 using 40mm IRC size B.G metal including curing, ramming etc, complete (adopting casual Labour) S.D	SD1	1855.70	1cum	432378
2	233 cum	Providing vibrated controlled Ready Mixed plain cement concrete M15 design mix (To be designed with the material to be used) using 20mm ISS size HBG metal including cost and conveyance of all materials to site including cement, handling charges for the same, mixing, including placing the pump in position, erecting the horizontal and vertical pipe line to the required distance and height, laying, compacting, providing cover blocks, finishing smooth the surface, including vibration charges, curing concrete, all other tools and plants employed and all other incidental charges etc. complete (Excluding cost and fabrication charges steel and form work) confirming to MORTH specifications as directed by the Engineer.	Br-11	2541.68	1cum	592211
3	47 sqm	Supplying and fixing premoulded Bituminous expansion pad of 12mm thick including cutting into proper shape, cost and conveyance, fixing in position where suitable opening have to be cut in the pad so as to seat in position and all other charges etc. complete wherever necessary.	Br-222	619.00	1sqm	29093
<b>TOTAL</b>						<b>1053682</b>

Signature of Tenderer