

பம்மல் நகராட்சி காஞ்சிபுரம் மாவட்டம்

ந.க.எண். 766 /2010 /இ1

நாள்: 25-10-2010

ஒப்பந்தப்புள்ளி அறிக்கை

1998 ஆம் ஆண்டு தமிழ்நாடு ஒளிவுமறைவற்ற ஒப்பந்தப்புள்ளிகள் சட்டம்
(தமிழ்நாடு சட்டம் 43/1998) கீழ் அறிவிக்கப்படுகிறது.

பம்மல் நகராட்சியின் சார்பாக செயல் அலுவலர் அவர்களால் பொது நிதியின் கீழ் குறிப்பிட்டுள்ள கீழ்க்கண்ட பணியினை செய்து முடிக்க மூடி முத்திரையிடப்பட்ட ஒப்பந்தப்புள்ளிகள் வரவேற்கப்படுகின்றன. பதிவு பெற்ற ஒப்பந்ததாரர்களிடமிருந்து 11.11.2010ம் தேதி வியாழக் கிழமை பிற்பகல் 3.00 மணிவரை (அலுவலக கடிதார நேரத்தின்படி) செயல் அலுவலர் அல்லது அவரது அங்கீகாரம் பெற்றவர்களால் பூர்த்தி செய்யப்பட்ட ஒப்பந்தப்புள்ளிகள் பெற்றுக் கொள்ளப்படும். பெறப்பட்ட ஒப்பந்தப்புள்ளிகள் அனைத்தும் அன்று பிற்பகல் 3.30 மணி அளவில் வருகை தந்திருக்கும் ஒப்பந்ததாரர்கள் முன்னிலையில் ஒப்பந்தப்புள்ளி உறைகள் திறக்கப்படும்.

பணி தொடர்பான ஒப்பந்தப்புள்ளி படிவங்கள் இந்நகராட்சி அலுவலகத்தில் வேலை நாட்களில் 10.11.2010 அன்று மதியம் 3.00 மணி வரை உரிய தொகை செலுத்தி பெற்றுக் கொள்ளலாம். பணி தொடர்பான இதர விவரங்களை நகராட்சி பொறியியல் பிரிவிலோ அல்லது <http://municipality.tn.gov.in/tenders>, <http://www.tenders.tn.gov.in> என்ற இணையத்தளத்தின் மூலமும் தெரிந்து கொள்ளலாம்.

ஒப்பந்தப்புள்ளி கோரும் பணியின் விவரம்

வ. எண்	பணிகளின் விவரம்	நகரமன்ற தீர்மான எண்	மதிப்பீட்டு தொகை ரூ.	ஒப்பந்தப்புள்ளி படிவ விலை ரூ.	காப்புறுதி தொகை 1% ரூ	பணி முடிக்கு ம் காலம்
1	3	4	5	6	7	8
1	எல்.ஐ.சி காலனி 3வது தெருவிற்கு தார்சாலை, கால்வாய் மற்றும் கல்வெட்டி அமைத்தல்	132/20.08.10	2,10,000/-	845/-	2100/-	45 நாட்கள்
2	வார்டு எண். 3, கரிகாலன் தெரு மற்றும் கஸ்தூரிபாய் தெரு சந்திப்பில் ஆர்.சி.சி கல்வெட்டி அமைத்தல்	143/30.09.10	1,00,000/-	338/-	1000/-	45 நாட்கள்
3	கேசவன் தெரு எம்.கே. முனுசாமி தெருவை இணைக்கும் சந்து சிமெண்ட் சாலை அமைத்தல்	148/30.09.10	50,000/-	169/-	500/-	45 நாட்கள்

நிபந்தனைகள்

1. தமிழ்நாடு ஒளிவு மறைவற்ற ஒப்பந்தப்புள்ளிகளின் சட்டம் 43/1998 மற்றும் விதிகள் 2000 படி ஒப்பந்தப்புள்ளிகள் பரிசீலிக்கப்படும்.
2. பணியின் தன்மை போன்ற பணியினை திட்ட மதிப்பிட்டு தொகைக்கு ஈடான தொகைக்கு செய்ய முடித்துள்ள அனுபவமுள்ள, தகுதிவாய்ந்தவராக இருத்தல் வேண்டும்.
3. பணியின் மதிப்பிட்டு தொகை போல இரண்டு மடங்கு தொகைக்கு பணி செய்த அனுபவம் கடந்த ஐந்து ஆண்டுகளில் ஏதேனும் 3 ஆண்டுகளில் பெற்றிருத்தல் வேண்டும்.
4. இதர நிபந்தனைகள் ஒப்பந்தப்புள்ளி படிவத்தில் தெரிந்து கொள்ளலாம்.

செயல் அலுவலர்
பம்மல் நகராட்சி
பம்மல், சென்னை – 75

பெறுநர்:

1. பதிவு செய்யப்பட்ட அனைத்து ஒப்பந்ததாரர்கள்,
பம்மல் மூன்றாம் நிலை நகராட்சி.
2. நகர மன்ற தலைவர், துணைத் தலைவர் மற்றும் அனைத்து உறுப்பினர்கள்,
பம்மல் மூன்றாம் நிலை நகராட்சி.
3. அலுவலக விளம்பரப் பலகையில் ஒட்டி விளம்பரம் செய்ய
4. செயல் அலுவலர், அனகாபுத்தூர், புழுதிவாக்கம், மறைமலைநகர், வளசரவாக்கம்
நகராட்சிகளின் – அலுவலக விளம்பர பலகைக்கு.

நகல்:

1. நகராட்சிகள் நிர்வாக இயக்குநர், எழிலகம், சேப்பாக்கம், சென்னை – 5
அவர்களின் தகவலுக்கு பணிந்து சமர்ப்பிக்கப்படுகிறது.
2. மண்டல நகராட்சிகள் நிர்வாக இயக்குநர், செங்கல்பட்டு மண்டலம்.
அவர்களின் தகவலுக்கு பணிந்து சமர்ப்பிக்கப்படுகிறது.
3. செயல் அலுவலர், அனகாபுத்தூர், புழுதிவாக்கம், மறைமலைநகர், வளசரவாக்கம்
நகராட்சிகளின் அலுவலக விளம்பர பலகைக்கு.

Date of Tender :

Issued to :

Schedule Cost Rs :

Challan No.& Date :

Municipal Engineer
Pammal Municipality

PAMMAL MUNICIPALITY **TENDER SCHEDULE**

- a) The quantities given here are those upon which lump sum tender cost of the work based but they are subject to alternations, omissions / deductions or additions as provided for the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates noted below this governing payment for the contract, as set forth in the preliminary a specification and other conditions as specification of the Chennai details standard specification and other conditions as specification of the contract.
- b) It is to be expressly understood that the measured work is to taken net (not with standing and customer practice to the contrary) according to the actual quantities when in places and finished according to the drawing or as many be ordered from time to time the cost calculated by measurement or weight, at the respective prices, without any additional charge for any necessary or contingent therewith. The rates quoted are for works in site and complete in every report.

Name of Work : Restoration of BT Road with Storm Water Drain and Culvert @ (Ward No. 2) L.I.C Colony 3rd Street

Estimate Cost : **210000**

Signature of Contractor

Name of Scheme : General Fund 2009-10

Earnest Money Deposit Rs : **2100**

Tender Date / Time :

PAMMAL MUNICIPALITY

Tender Schedule for the Work of Restoration of BT Road with Storm Water Drain and Culvert @ (Ward No. 2) L.I.C Colony 3rd Street

Est Amt: 210000/-

SI No	Qty	Description of Work	Unit Per	Rate in Figures	Rate in Words	Amount	Remarks
1	78.40	Earthwork excavation in all soils except hard rock soil including de-watering wherever necessary and refilling the earth after completion of work etc., complete as per the standard specification.	1M ³ (One Cubic Metre)				
2	17.20	Filling with dry river Sand including cost and conveyance of material, and labour for placing, watering and consolidation etc., complete as per specification	1M ³ (One Cubic Metre)				
3	18.76	Plain cement concrete 1:5:10 (one cement five sand and ten aggregate) mix using 40 mm ISS HBG metal including cost of material, conveyance and labour for mixing, placing and consolidation and watering for curing etc., complete as per specification	1M ³ (One Cubic Metre)				
4	252.00	Providing Steel centering and shuttering using 10cm to 15cm dia casurina post and M.S sheet of size 60cm X 90 cm etc., complete as per standard specification for Drain	1M ² (One Square Metre)				
5	27.52	Providing Steel centering and shuttering using 10cm to 15cm dia casurina post and M.S sheet of size 60cm X 90 cm etc., complete as per standard specification for Culverts	1M ² (One Square Metre)				
6	28.80	Plain cement concrete 1:3:6 (one cement three sand and six aggregate) mix using 20mm ISS HBG metal including cost and conveyance of material, and labour for mixing, placing, consolidation and watering for curing etc., complete as per specification	1M ³ (One Cubic Metre)				
7	4.73	Plain cement concrete 1:2:4 (one cement two sand and four aggregate) mix using 20 mm ISS HBG metal including cost and conveyance of material, and labour for mixing, placing, consolidation and watering for curing etc., complete as per specification	1M ³ (One Cubic Metre)				
8	356.00	Supplying, fabricating, and placing in position of mild steel for all reinforced cement concrete works including cost and conveyance of steel and binding wire and all other labour charges for cutting bending tying etc. complete as per standard specification.	1M ³ (One Cubic Metre)				

No. of Corrections :
No. of Overwrittings :

Signature of Contractor

9	2.07	Reinforced cement concrete 1:2:4 (one cement two sand and four aggregate) mix using 20 mm ISS HBG metal including cost and conveyance of material, and labour for mixing, placing, consolidation and watering for curing etc., complete as per specification	1KG (One Kilogram)				
10	148.50	Flooring plastering with cm 1:5 (one cement and five sand) including cost and conveyance of material and labour charges for placing curing etc., complete as per specification	1M ² (One Square Metre)				
11	38.25	Providing RCC Precast slab in Cement Mortar 1:2:4 mix using 20mm ISS HBG metal including cost of material and conveyance charges and vibrator including all labour charges and all other incidental charges etc., complete as per standar specification(0.075m thick)	1M ² (One Square Metre)				
12	52.27	Removal of excess earth with minimum lead of 2Km including labour, Transport and loading and unloading etc complete as per standard specification	1M ³ (One Cubic Metre)				

(Approved (12) Twelve Items Only)

No. of Corrections :

No. of Overwrittings :

Signature of the Contractor

**Overseer
Pammal Municipality**

**Municipal Engineer
Pammal Municipality**